Northumberland to Dummer (0154) Line Rebuild Project

EVERS©URCE

Improving the Reliability of the Electric System across New Hampshire

Project Overview

As part of our ongoing investments to deliver reliable energy to our customers and communities, Eversource will be replacing existing wooden pole structures in Northumberland, Stark, and Dummer, N.H. This work will be taking place within the existing right-of-way (power line corridor) of the O154 transmission line, a 115kV line built in 1946 that is 12 miles long and starts at the Lost Nation Substation in Northumberland and terminates at the Paris Substation in Dummer. A total of 138 structures will be removed or replaced, and fiber optic cable, known as Optical Ground Wire (OPGW) will be installed the length of the line.

Always Working to Serve You Better

Eversource is making a significant investment in electric infrastructure in order to provide enhanced system reliability for local communities. The new steel structures will be more resilient and will be less susceptible to woodpecker damage, insect damage or pole rot. The new structures will also have reliability enhancements to protect the system from damage due to severe weather, including floods.



Example of structure to be installed

The OPGW that is being installed on this line and across Eversource's transmission system enables faster and more reliable communication between Eversource's substations (the communication is not related to any cellular or telecom service). This communication allows increased visibility of our system, quicker responses time for system issues, increased automation, reduces outages and their length, and overall improves reliability across the electric system.

What You Can Expect

We intend to rebuild the line in the same location it is today, with some variations. While structure height increases are unavoidable, we attempted to minimize them wherever possible, while ensuring current electrical standards and safety clearances are met and balancing other important considerations such as environmental impacts. Overall, major tree removals are not anticipated for construction related activity, though some may be necessary for access in various locations.

Anticipated Project Schedule

(schedule is subject to change due to weather or other unexpected circumstances)

- State and Federal Permitting: beginning 4th Quarter 2021
- Local Permitting: 2nd Quarter 2022
- Construction: 3rd Quarter 2022 through 4th Quarter 2023
- Site Restoration: 3rd and 4th Quarter 2023

Project Representatives are available to answer your questions. Please call at your convenience.

